TECHNICAL DOCUMENTATION

APPLIED AI · RAG

2026 EDITION

Hypothetical cases — kitchens, leaks and renovation decisions

REFERENCE DOCUMENTATION FOR THE AI ASSISTANT

RIANSARES 4R

Tarancón · 16400 · Cuenca · Spain

Documentation & AI: Germán Caballero

riansares.com **athagon.tech**

Hypothetical cases — kitchens, leaks and renovation decisions

K-21 — Leak near a dishwasher

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Water appears beneath a built-in appliance after every wash.

Checks: Check supply connection, hose, drainage, joints and safe removal options.

Possible scope: Specific repair and review of furniture damage.

Decision criterion: Do not replace flooring without identifying the source.

Evidence to retain: Photos during use, of the component and of testing.

K-22 — Constantly leaking tap

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: The tap drips even when closed.

Checks: Distinguish cartridge, flexible hoses and connections; assess general condition.

Possible scope: Tap repair or replacement after diagnosis.

Decision criterion: Do not quote for a complete renovation.

Evidence to retain: Component and shut-off test.

K-23 — Kitchen needs new flooring

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Floor tiles are broken while a pipe is being repaired.

Checks: Base condition, moisture and flooring continuity.

Possible scope: Local repair or complete floor tiling according to actual damage.

Decision criterion: Do not lay flooring over a damp base.

Evidence to retain: Damage plan and measurements.

K-24 — Relocating a sink

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: The aim is to place the sink beneath another window.

Checks: Drainage gradient, water supply and distances.

Possible scope: New routing if feasible and accessible for inspection.

Decision criterion: Do not decide solely on appearance.

Evidence to retain: Sketch and levels.

K-25 — Detached finish behind the sink

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: The wall sounds hollow and there is longstanding damp.

Checks: Check adhesion, moisture source and substrate.

Possible scope: Strip back, dry and apply suitable wall tiling.

Decision criterion: Do not bond onto loose tiles.

Evidence to retain: Photos of each layer.

K-26 — Partial renovation retaining cabinets

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: The client has a limited budget and wants pipe repairs.

Checks: Access and potential to salvage cabinets.

Possible scope: Plumbing replacement and finishing without replacing everything.

Decision criterion: Separate essential/optional expenses.

Evidence to retain: Inventory of retained cabinets.

K-27 — Appliances and insufficient power

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: A hob, oven and dishwasher are added.

Checks: Installation characteristics and power/circuits.

Possible scope: Electrical adaptation by an authorised professional if appropriate.

Decision criterion: Do not use a single multi-socket adaptor as the solution.

Evidence to retain: Installation report.

K-28 — Unventilated utility room

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Laundry area with odours and condensation.

Checks: Connections, leaks, extraction and ambient humidity.

Possible scope: Water and ventilation solution followed by finishes.

Decision criterion: Do not recommend only a dehumidifier.

Evidence to retain: Comparative measurements.

K-29 — Water-swollen cabinet

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Panels beneath the sink are deformed.

Checks: Leak repair and material condition.

Possible scope: Dry and repair or replace affected panels.

Decision criterion: Do not assure that original dimensions will return.

Evidence to retain: Photos and replacement scope.

K-30 — Cracked worktop

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: The worktop has cracked after base movement.

Checks: Supports, joints and movement source.

Possible scope: Specialist repair or replacement according to material and risk.

Decision criterion: Do not seal a structural crack without diagnosis.

Evidence to retain: Views of supports and damage.

K-31 — Renovation without removing tiles

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: The aim is a new appearance with minimal rubble.

Checks: Adhesion, damp, thicknesses and finishing details.

Possible scope: Compatible solution respecting services.

Decision criterion: Do not hide leaks with decorative finishes.

Evidence to retain: System data sheet and tests.

K-32 — Two homes affected

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Replacing a kitchen drainage stack affects the floor below.

Checks: Ownership and access between homes.

Possible scope: Coordinate repair and damage reinstatement.

Decision criterion: Do not assign responsibility without a report.

Evidence to retain: Records and routing.