TECHNICAL DOCUMENTATION

APPLIED AI · RAG

2026 EDITION

Hypothetical cases — damp, rehabilitation and structures

REFERENCE DOCUMENTATION FOR THE AI ASSISTANT

RIANSARES 4R

Tarancón · 16400 · Cuenca · Spain

Documentation & AI: Germán Caballero

riansares.com **athagon.tech**

Hypothetical cases — damp, rehabilitation and structures

H-21 — Roof leaks after wind

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Stains appear after wind-driven rain.

Checks: Roof junctions, façade flashings and gutters.

Possible scope: Repair the verified point and monitor.

Decision criterion: Do not assume roof tiles are responsible.

Evidence to retain: Rainfall photos and location.

H-22 — Cold floor with an odour

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Ground floor with a persistent damp smell.

Checks: Ventilation, water beneath the concrete floor base and salts.

Possible scope: Diagnosis before insulation or finishes.

Decision criterion: Do not encapsulate moisture without a drying plan.

Evidence to retain: Hygrometer readings and plans.

H-23 — Stone wall with salts

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Render is detaching from an old wall.

Checks: Moisture, salts and mortar compatibility.

Possible scope: Conservation/stripping back and compatible materials.

Decision criterion: Do not prescribe a universal mortar.

Evidence to retain: Wall characterisation.

H-24 — New crack when enlarging an opening

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: A crack appears above the opening after work.

Checks: Loads and continuity, technical assessment.

Possible scope: Stop risky work and consult a professional.

Decision criterion: Do not apply filler before assessment.

Evidence to retain: Photographs and assessment.

H-25 — Mould after internal insulation

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Mould appears at a floor-structure junction.

Checks: Thermal bridge, ventilation and moisture.

Possible scope: Review continuity and hygrothermal conditions.

Decision criterion: Do not add more insulation without diagnosis.

Evidence to retain: Measurements and construction detail.

H-26 — Patio leaks into a basement

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Stains below ground level during heavy rain.

Checks: Drainage, junctions and lateral water pressure.

Possible scope: Water management solution compatible with the ground.

Decision criterion: Waterproof paint does not replace drainage.

Evidence to retain: Tests and rainwater routes.

H-27 — Window condensation

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Recurring droplets on glass in the morning.

Checks: Indoor humidity, ventilation and thermal bridges.

Possible scope: Adjust ventilation and envelope according to cause.

Decision criterion: Do not diagnose a roof leak.

Evidence to retain: Relative humidity and photograph.

H-28 — Swollen plaster after an old leak

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: The pipe was repaired but plaster remains soft.

Checks: Drying and material condition.

Possible scope: Remove unstable material and finish when appropriate.

Decision criterion: Do not paint without checking the substrate.

Evidence to retain: Drying follow-up.

H-29 — Roof with wet insulation

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Moisture is discovered within roof layers.

Checks: Source and extent, safe access.

Possible scope: Repair watertightness and replace damaged layers according to assessment.

Decision criterion: Do not enclose wet insulation.

Evidence to retain: Opening-up and closing-up sequence.

H-30 — House closed for years

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Damp smell and salts on walls.

Checks: Ventilation, rising damp, leaks and roof.

Possible scope: Diagnosis by area and rehabilitation by priority.

Decision criterion: Do not promise a ready-to-live-in home after painting.

Evidence to retain: Damage map and priorities.

Industry references and scope

- EPA.
- CTE_HS.

The references provide general context and do not establish that Riansares 4R has carried out work. Technical requirements must be verified for the applicable type of intervention and jurisdiction.