TECHNICAL DOCUMENTATION

APPLIED AI · RAG

2026 EDITION

Hypothetical cases — offices, commercial premises and public spaces

REFERENCE DOCUMENTATION FOR THE AI ASSISTANT

RIANSARES 4R

Tarancón · 16400 · Cuenca · Spain

Documentation & AI: Germán Caballero

riansares.com **athagon.tech**

Hypothetical cases — offices, commercial premises and public spaces

O-21 — Noisy office

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Partition renovation near workers.

Checks: Hours, circulation and critical activities.

Possible scope: Work phases and area isolation.

Decision criterion: Do not promise zero noise.

Evidence to retain: Agreed plan.

O-22 — Premises with narrow access

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Entrance with a step and narrow door.

Checks: Geometry, escape routes and accessibility.

Possible scope: Adaptation design according to requirements.

Decision criterion: Do not propose a generic ramp without measurements.

Evidence to retain: Dimensioned plan.

O-23 — School with deteriorated flooring

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Slippery flooring in a school changing room.

Checks: Slipping, use and cleaning conditions.

Possible scope: Replacement compatible with safety and activity.

Decision criterion: Do not focus solely on tile colour.

Evidence to retain: Data sheet and acceptance record.

O-24 — Office toilet fault

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: The only toilet stops working.

Checks: Availability of alternatives and interruption duration.

Possible scope: Priority repair and contingency.

Decision criterion: Do not continue operations while ignoring essential facilities.

Evidence to retain: Repair record.

O-25 — Small shop with damaged façade

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Loose finish above the entrance.

Checks: Risk of material falling onto the public.

Possible scope: Protect the passage and repair appropriately.

Decision criterion: Do not delay safety measures.

Evidence to retain: Risk report.

O-26 — Damp gym

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Mould near communal showers.

Checks: Extraction, condensation and possible leaks.

Possible scope: Moisture control and hygienic finishes.

Decision criterion: Do not cover mould without resolving the source.

Evidence to retain: Measurements and cleaning plan.

O-27 — Industrial building with translucent roof

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Leak near a fragile panel.

Checks: Height and access risks.

Possible scope: Inspection using safe working systems.

Decision criterion: Do not recommend walking on fragile panels.

Evidence to retain: Procedure and photos.

O-28 — Noisy communal patio

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Flooring replacement in a communal area.

Checks: Hours, access, rubble and drainage.

Possible scope: Phases and communication with neighbours.

Decision criterion: Do not change gradients without studying drainage.

Evidence to retain: Phasing plan.

O-29 — Restaurant toilet

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Renovation during partial closure.

Checks: Hygiene, supply, escape routes, accessibility.

Possible scope: Execution in authorised phases.

Decision criterion: Do not promise opening without necessary approval.

Evidence to retain: Test record.

O-30 — Pool with deteriorated joints

Hypothetical assessment case, not completed work or a service committed to by Riansares 4R.

Situation: Suspected pool-shell leaks.

Checks: Actual source and substrate condition.

Possible scope: Repair according to diagnosis.

Decision criterion: Do not confuse joints with overall watertightness.

Evidence to retain: Controlled tests.

Industry references and scope

- CTE_SUA.
- HSE_HEIGHT.

The references provide general context and do not establish that Riansares 4R has carried out work. Technical requirements must be verified for the applicable type of intervention and jurisdiction.