TECHNICAL DOCUMENTATION

APPLIED AI · RAG

2026 EDITION

Riansares 4R — additional structured data

REFERENCE DOCUMENTATION FOR THE AI ASSISTANT

RIANSARES 4R

Tarancón · 16400 · Cuenca · Spain

Documentation & AI: Germán Caballero

riansares.com **athagon.tech**

Riansares 4R — additional structured data

Usage rule

These amounts are not Riansares 4R rates or binding offers. They are dated references from market guides and a technical work item. Before quoting, review measurements, condition, access, quality levels, waste, licences, VAT, margin and risks.

Price table

ID	Category	Description	Unit	Low	Central	High	Source
P-001	Complete renovation	Home, indicative mid-range	EUR/m2	400	525	650	SRC-HAB-VIVIENDA
P-002	Old house	Complete renovation without structural work or layout changes	EUR/m2	350	416.66	450	SRC-HAB-ANTIGUA
P-003	Old house	Complete renovation with structural strengthening	EUR/m2	533.33	533.33	533.33	SRC-HAB-ANTIGUA
P-004	Old house	Complete renovation with layout changes	EUR/m2	600	600	600	SRC-HAB-ANTIGUA
P-005	Kitchen	Kitchen renovation 4 m2	EUR/project	3850	3850	5000	SRC-HAB-COCINA
P-006	Kitchen	Kitchen renovation 7 m2	EUR/project	5600	6000	9000	SRC-HAB-COCINA
P-007	Kitchen	Kitchen renovation 10 m2	EUR/project	7000	8100	11000	SRC-HAB-COCINA
P-008	Kitchen	Kitchen renovation 12 m2	EUR/project	7800	8500	12000	SRC-HAB-COCINA
P-009	Bathroom	Small bathroom 2 m2	EUR/project	1560	1560	1560	SRC-HAB-BANO
P-010	Bathroom	Bathroom without building work 4 m2	EUR/project	2000	2000	2000	SRC-HAB-BANO
P-011	Bathroom	Bathroom without removing tiles 4 m2	EUR/project	2900	2900	2900	SRC-HAB-BANO
P-012	Bathroom	Bathroom with mid-range finishes 5 m2	EUR/project	4250	4250	4250	SRC-HAB-BANO
P-013	Bathroom	Bathroom with high-end finishes 6 m2	EUR/project	4860	4860	4860	SRC-HAB-BANO
P-014	Laminate flooring	Mid-range quality including labour	EUR/m2	25	30	30	SRC-HAB-LAMINADO
P-015	Laminate flooring	Published general range	EUR/m2	20	30	65	SRC-HAB-LAMINADO
P-016	Painting	White painting of a flat	EUR/m2	10	11	12	SRC-HAB-PINTURA
P-017	Painting	Painting a flat 100 m2	EUR/project	1300	1300	1300	SRC-HAB-PINTURA
P-018	Demolition	Manual wall-tile removal DRA010	EUR/m2	8.9	8.9	8.9	SRC-CYPE-DEMO-ALIC

Non-binding example quotations

B-001 — Complete renovation of an 80 m2 home

- **Low range:** 32,000 EUR
- **Base:** 42,000 EUR
- **High range:** 52,000 EUR
- **Documentary basis:** P-001, SRC-HAB-VIVIENDA
- **Assumptions:** mid-range quality, no structural work, moderate layout changes, normal access
- **Exclusions:** VAT, technical design where required, fees, asbestos, structural damage
- **Calculation:** 80 m2 multiplied by the 400–650 EUR/m2 range; the baseline approximates the published example starting at 40.000 EUR.

B-002 — 120 m2 old house without structural strengthening

- **Low range:** 42,000 EUR
- **Base:** 50,000 EUR
- **High range:** 54,000 EUR
- **Documentary basis:** P-002, SRC-HAB-ANTIGUA
- **Assumptions:** no structural work, no extensive layout changes, mid-range quality
- **Exclusions:** complete roof, foundations, structural damp, technical design and fees
- **Calculation:** 120 m2 at 350–450 EUR/m2. The source publishes an itemised 41.900 EUR example.

B-003 — 120 m2 old house with structural work and layout changes

- **Low range:** 64,000 EUR
- **Base:** 72,000 EUR
- **High range:** 100,000 EUR
- **Documentary basis:** P-003, P-004, SRC-HAB-ANTIGUA
- **Assumptions:** localised strengthening, layout changes, complete services
- **Exclusions:** undetected major defects, complete roof, specialist foundations
- **Calculation:** Published references reach 533–600 EUR/m2 and the guide itself states that extensive work may reach 100.000 EUR.

B-004 — 7 m2 kitchen, mid-range quality

- **Low range:** 5,600 EUR

- **Base:** 6,500 EUR
- **High range:** 9,000 EUR
- **Documentary basis:** P-006
- **Assumptions:** basic cabinets, no load-bearing wall, nearby services
- **Exclusions:** premium appliances, premium worktop, opening into the living room
- **Calculation:** Range taken directly from the consulted price guide.

B-005 — 5 m2 bathroom, mid-range quality

- **Low range:** 4,250 EUR
- **Base:** 5,200 EUR
- **High range:** 7,500 EUR
- **Documentary basis:** P-012, P-013
- **Assumptions:** retained layout, standard waterproofing, mid-range sanitary fittings
- **Exclusions:** stack replacement, floor-structure damage, luxury furniture
- **Calculation:** The baseline extends the published table to include common contingencies that vary between projects.

B-006 — Laminate flooring over 70 m2

- **Low range:** 1,750 EUR
- **Base:** 2,100 EUR
- **High range:** 4,550 EUR
- **Documentary basis:** P-014, P-015
- **Assumptions:** reasonably flat substrate, mid-range quality
- **Exclusions:** removal, extensive levelling, special skirting, door trimming
- **Calculation:** 70 m2 multiplied by 25–30 EUR/m2; high end based on the general range of 65 EUR/m2.

B-007 — White painting of a 100 m2 flat

- **Low range:** 1,000 EUR
- **Base:** 1,300 EUR
- **High range:** 2,800 EUR
- **Documentary basis:** P-016, P-017
- **Assumptions:** walls in reasonable condition, standard protection
- **Exclusions:** active damp, smoothing all walls throughout the home, decorative painting

- **Calculation:** The baseline uses the 1.300 EUR example; the high end allows additional preparation and repair.

B-008 — Removal of 30 m2 of wall tiling

- **Low range:** 267 EUR
- **Base:** 650 EUR
- **High range:** 1,200 EUR
- **Documentary basis:** P-018
- **Assumptions:** manual removal, normal access
- **Exclusions:** skip and fees unless specified, complex protection, removal of services
- **Calculation:** The minimum is 30 × 8,90 EUR/m2 according to the technical work item; baseline and high figures add logistics, protection and actual site management.

Recommended fields for an actual quotation

```
{
"id": "R4R-BUDGET-YYYY-NNN",
"date": "YYYY-MM-DD",
"location": "municipio",
"scope": [],
"measurements": [],
"line_items": [],
"materials_quality": "basic|medium|high|custom",
"access": "direct|limited|manual",
"waste_included": true,
"permit_responsibility": "client|contractor|technician",
"vat_rate": 21,
"vat_basis_note": "",
"exclusions": [],
"hidden_damage_rule": "",
"payment_milestones": [],
"estimated_duration_days": null,
"valid_until": "YYYY-MM-DD"
}
```

Caution criteria

- A price per m² supports comparison, not quotations without measurements.

- The CYPE work item describes a specific configuration and does not automatically include all business costs.
- Market guides aggregate heterogeneous projects.
- References must retain their date and source.
- VAT and licences are verified for each transaction.